

ALUMIL SA THERMAL PERFORMANCE TEST REPORT

SCOPE OF WORK

S77 FIXED WINDOW

REPORT NUMBER

J6339.02-116-46 R0

TEST DATE

07/30/19

ISSUE DATE

09/30/19

RECORD RETENTION END DATE

07/30/24


PAGES

19

DOCUMENT CONTROL NUMBER

RTTDS-R-AMER-Test-2822(c) (07/07/18)

©2017 INTERTEK



TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

REPORT ISSUED TO

ALUMIL SA

Iatrou Gogousi 8 GR 56429

Thessaloniki, GR 56429 (Greece)

SECTION 1

SCOPE

SERIES/MODEL: S77 Fixed Window

TYPE: Fixed

Intertek Building & Construction (Intertek B&C) was contracted by Alumil SA to evaluate the thermal performance per AAMA 1503-09. The purpose of this testing was to evaluate the Condensation Resistance and Thermal Transmittance. Results obtained are tested values and were secured by using the designated test method. Testing was conducted at Intertek B&C test facility in York, Pennsylvania. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

Condensation Resistance Factor - Frame (CRFf):	77
Condensation Resistance Factor - Glass (CRFg):	72
Thermal Transmittance (U):	0.32 Btu/hr·ft ² ·F

For INTERTEK B&C:

COMPLETED BY	Ryan P. Moser
TITLE	Senior Technician
SIGNATURE	
DATE	09/30/19

RPM:pan

REVIEWED BY	Shon W. Einsig
TITLE	Technician Team Leader, IIRC
SIGNATURE	
DATE	09/30/19

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 3

TEST SPECIMEN SUMMARY

SERIES/MODEL	S77 Fixed Window
TYPE	Fixed
OVERALL SIZE	47-1/4" x 59"
TEST SAMPLE SUBMITTED BY	Client

SECTION 4

TEST METHOD

The specimens were evaluated in accordance with the following:

AAMA 1503-09, *Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections*

SECTION 5

MATERIAL SOURCE/INSTALLATION

The test specimen was provided by the client. Representative samples of the test specimen will be retained by Intertek B&C for a minimum of two years from the test completion date.

Test Chamber Installation

The test sample was installed in a vertical orientation, the exterior of the specimen was exposed to the cold side.

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Ryan P. Moser	Intertek B&C
Shon W. Einsig	Intertek B&C

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 7

TEST SAMPLE DESCRIPTION

Frame

MATERIAL	AT (1.27"): Aluminum with Thermal Breaks - All Members		
SIZE	47-1/4" x 59"		
DAYLIGHT OPENING	42-5/8" x 54-1/2"	GLAZING METHOD	Interior
EXTERIOR COLOR	White	EXTERIOR FINISH	Paint
INTERIOR COLOR	White	INTERIOR FINISH	Paint
CORNER JOINERY	Mitered / Keys & Stakes / Sealed		

Glazing Information

LAYER 1	1/4"	CL Extereme 60/28 II (e=0.026*, #2)	
GAP 1	0.56"	TP-D: Saint-Gobain Swisspacer	100% Air*
LAYER 2	1/4"	Clear	
GAS FILL METHOD		N/A*	
DESICCANT		Yes	

**Stated per Client/Manufacturer*

N/A Non-Applicable

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 7 (CONTINUED)

TEST SAMPLE DESCRIPTION (CONTINUED)

Weatherstripping

DESCRIPTION	QUANTITY	LOCATION
Glazing gasket	1 Row	Interior glazing perimeter
Glazing gasket	1 Row	Exterior glazing perimeter

Hardware

DESCRIPTION	QUANTITY	LOCATION
No hardware		

Drainage

DRAINAGE METHOD	SIZE	QUANTITY	LOCATION
No visible weeps			

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 8

CONDENSATION RESISTANCE FACTOR

1. Average Metering Room Air Temperature (th)	69.79 F
2. Average Cold Side Air Temperature (tc)	-0.38 F
3. Average of 14 Pre-Specified Frame Temperatures (FTp)	53.48 F
4. Average of 4 Roving Thermocouples (FTr)	49.68 F
5. Weighting Factor (W)	0.035
6. Weighted Frame Temperature (FT)	53.35 F
7. Average Glass Temperature (GT)	50.19 F
8. Condensation Resistance Factor – Frame (CRFf)	77
9. Condensation Resistance Factor – Glass (CRFg)	72

The CRF number was determined to be 72 (on the size as reported). When reviewing this test data, it should be noted that the glass temperature (GT) was colder than the frame temperature (FT) therefore controlling the CRF number. Refer to the 'CRF Report' page and the 'Thermocouple Location Diagram' page of this report.

SECTION 9

THERMAL TRANSMITTANCE

1. Average Metering Room Air Temperature (th)	69.79 F
2. Average Cold Side Air Temperature (tc)	-0.38 F
3. Measured Static Pressure Difference Across Test Specimen	0.00" \pm 0.04" H ₂ O
4. Test Specimen Projected Area (As)	19.36 ft ²
5. Total Measured Input into Metering Box (Qtotal)	509.56 Btu/hr
6. Total Correction	71.83 Btu/hr
7. Net Specimen Heat Loss (Qs)	437.73 Btu/hr
8. Thermal Transmittance (U)	0.32 Btu/hr·ft ² ·F

SECTION 10

TEST DURATION

1. The environmental systems were started at 13:00 hours, 07/29/19.
2. The test parameters were considered stable for two consecutive four hour test periods from 22:01 hours, 07/29/19 to 06:01 hours, 07/30/19.
3. The thermal performance test results were derived from 02:01 hours, 07/30/19 to 06:01 hours, 07/30/19.

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19


SECTION 11

TEMPERATURE AND CONDENSATION RESISTANCE CALCULATION

Time	04:01	04:31	05:01	05:31	06:01	Average
Pre-Specified Thermocouples - Frame						
1	49.16	49.17	49.21	49.20	49.23	49.19
2	50.82	50.86	50.89	50.88	50.88	50.86
3	50.50	50.51	50.51	50.53	50.53	50.52
4	56.32	56.29	56.30	56.33	56.39	56.33
5	56.84	56.85	56.88	56.88	56.88	56.87
6	57.01	57.01	57.04	57.02	57.03	57.02
7	55.66	55.66	55.67	55.69	55.67	55.67
8	56.51	56.53	56.51	56.55	56.55	56.53
9	54.50	54.50	54.52	54.53	54.52	54.52
10	54.50	54.50	54.52	54.53	54.52	54.52
11	52.31	52.29	52.33	52.35	52.38	52.33
12	53.09	53.11	53.13	53.13	53.13	53.12
13	49.81	49.82	49.80	49.84	49.86	49.83
14	51.40	51.39	51.40	51.42	51.41	51.40
FTp	53.46	53.46	53.48	53.49	53.50	53.48
Pre-Specified Thermocouples - Glass						
15	38.71	38.74	38.73	38.78	38.77	38.75
16	54.28	54.28	54.28	54.33	54.31	54.30
17	47.26	47.30	47.27	47.31	47.29	47.29
18	53.75	53.74	53.76	53.78	53.75	53.76
19	55.26	55.28	55.30	55.31	55.28	55.29
20	51.77	51.76	51.74	51.77	51.78	51.76
GT	50.17	50.18	50.18	50.21	50.20	50.19
Cold Point (Roving) Thermocouples						
21	49.20	49.20	49.20	49.20	49.20	49.20
22	49.40	49.40	49.40	49.40	49.40	49.40
23	49.80	49.80	49.80	49.80	49.80	49.80
24	50.30	50.30	50.30	50.30	50.30	50.30
FTr	49.68	49.68	49.68	49.68	49.68	49.68
W	0.035	0.035	0.035	0.035	0.035	0.035
FT	53.33	53.33	53.35	53.36	53.37	53.35
Warm Side - Room Ambient Air Temperature						
	69.78	69.79	69.79	69.78	69.81	69.79
Cold Side - Room Ambient Air Temperature						
	-0.37	-0.43	-0.26	-0.38	-0.42	-0.37
Condensation Resistance Factor						
CRFf	77	77	77	77	77	77
CRFg	72	72	72	72	72	72

TEST REPORT FOR ALUMIL SA
Report No.: J6339.02-116-46 R0
Date: 09/30/19

SECTION 12
THERMOCOUPLE LOCATION DIAGRAM



COLD POINT LOCATIONS	
21	49.20
22	49.40
23	49.80
24	50.30

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 13

GLAZING DEFLECTION

	FRAME
EDGE GAP WIDTH	0.56"
ESTIMATED CENTER GAP WIDTH upon receipt of specimen in laboratory (after stabilization)	0.53"
CENTER GAP WIDTH at laboratory ambient conditions on day of testing	0.53"
CENTER GAP WIDTH at test conditions	0.41"

Glass collapse determined using a digital glass and air space meter

The sample was inspected for the formation of frost or condensation, which may influence the surface temperature measurements. The sample showed no evidence of condensation/frost at the conclusion of the test.

Required annual calibrations for the Intertek B&C, 'thermal test chamber' (ICN 000001) in York, Pennsylvania were last conducted in May 2019 in accordance with Intertek B&C calibration procedure. A CTS Calibration verification was performed August 2018. A Metering Box Wall Transducer and Surround Panel Flanking Loss Characterization was performed August 2018.

ANSI/NCSL Z540-2-1997 type B uncertainty for this test was 2.00%.

Prior to testing the specimen was sealed with silicone on the interior side and checked for air infiltration per Section 9.3.4.


TEST REPORT FOR ALUMIL SA


Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 14
DRAWINGS

The test specimen drawings which follow have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.





38 [1.50"]

202-11-151-01

200-11-156-01


S60435



313-10-030-00

200-01-154-11

S77510

313-25-021-00





S77510
Frame width



Report #: J6339-116-46
Date: 07/30/2019
Verified by: *Bryan P. Moser*

2 pieces

S77510
Frame height

2 pieces

S60435
Glazing bead width

2 pieces

S60435
Glazing bead height


2 pieces

202-11-151-01




External glass gasket

200-11-156-01



Internal glass gasket

200-01-154-11




Gasket for glazing bead

220-11-449-12




Gasket for glazing bead

~~290-00-005-00~~




~~5mm Shim~~

~~290-00-002-00~~




~~2mm Shim~~

~~290-77-001-00~~




~~Glazing bridge~~

~~290-77-002-00~~



~~Glazing bridge~~

313-10-030-00



Glazing foam 30x10 mm



Foam Rubber

313-25-021-00



NRG bar 25x21


Expanded
Polystyrene

200-06-860-01		External glazing gasket
200-08-004-01		Internal glazing gasket


S77510

intertek
Total Quality. Assured.


Report #: J6339-116-46
Date: 07/30/2019
Verified by: *Ryan P. Moser*



S60435




S60440



intertek
Total Quality. Assured.

Report #: J6339-116-46
Date: 07/30/2019
Verified by: *Bryan P. Moser*



DETAIL FOR THERMAL MODELING OF
SAINT-GOBAIN SWISSPACER (TP-D)

TEST REPORT FOR ALUMIL SA

Report No.: J6339.02-116-46 R0

Date: 09/30/19

SECTION 15

REVISION LOG

REVISION #	DATE	PAGES	REVISION
.02 R0	09/30/19	N/A	Original Report Issue